

ADDENDUM NO. 2
September 17, 2018
224387

RE: **TOWN OF ROXBURY, VERMONT**
BULL RUN ROAD SLIDE SLOPE STABILIZATION

FROM: DuBOIS & KING, INC.
P.O. Box 339
Randolph, Vermont 05060
(802) 728-3376

TO: **Prospective Bidders**

This Addendum forms part of the Contract Documents and modifies the original Bidding Documents issued by the Town of Roxbury, for the Bull Run Road Slide Slope Stabilization project dated August 31, 2018. **Acknowledge receipt of this Addendum in the space provided on Page 1 of the Bid Form. Failure to do so will subject the Bidder to disqualification.**

I. Pre-Bid Meeting

II. Contract Documents (Plan) Changes

III. Contract Documents (Specification) Changes

IV. Questions & Answers

V. Additional Information/Clarifications

- a. The Owner reserves the right to adjust the thickness of the Granular Borrow (Item 203.32) and Stone Fill, Type II (Item 613.11) as shown on Sheets 3 and 10, at the Unit Prices submitted on the bid form.
- b. The courses of riprap heavy type (or the alternate concrete blocks) shall be doweled together, as detailed for the base course on Sheet 10 (which is doweled into the ledge). The Owner reserves the right to increase the quantity of dowels at the unit price shown on the BID FORM (Item 507.16).
- c. The Contractor is advised that excavation to install Rip Rap, Heavy Type Wall or Concrete Blocks shall be constructed in short segments of minimal length (i.e., maximum of 10 feet where feasible) with materials ready to backfill and cover. The Contractor is advised that a cut slope of this depth has the potential to become unstable and the Contractor shall take all appropriate safety measures.

This document constitutes Addendum 2 for this project.